

Product data sheet
Characteristics

PK18GTAL

Equipment ground bar kit, QO/HOM load center, NQ/NF panelboard, 19 terminals, extra feed through lug



Main

Product line	QO
Product type	Load Center Grounding Bar Assembly

Complementary

Number of connectors	19
Wire size	AWG 14...AWG 4 copper AWG 12...AWG 4 aluminium AWG 4...AWG 1 aluminium/copper
Provided equipment	2 QO 1 screw
Bar length	8.82 in (224 mm)
Maximum length of segment	3.15 in (80 mm)
Device mounting	Mounting holes back of enclosure
Tightening torque	30 lb.in Mounting screw 30 lb.in 20 lb.in, AWG 14...AWG 10, copper 20 lb.in, AWG 12...AWG 10, aluminium 35 lb.in, AWG 6...AWG 4 25 lb.in, AWG 8 25 lb.in, AWG 14...AWG 12, copper 25 lb.in, AWG 12...AWG 10, aluminium

Ordering and shipping details

Category	00102 - QO LC ACCESSORIES
Discount Schedule	DE3A
GTIN	00785901440888
Nbr. of units in pkg.	5

* Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Package weight(Lbs)	0.37 lb(US) (0.17 kg)
Returnability	Yes
Country of origin	US

Packing Units

Package 1 Height	1.00 in (2.540 cm)
Package 1 width	4.00 in (10.160 cm)
Package 1 Length	8.50 in (21.590 cm)

Offer Sustainability

EU RoHS Directive	Compliant EU RoHS Declaration
Mercury free	Yes
RoHS exemption information	Yes
China RoHS Regulation	China RoHS declaration Product out of China RoHS scope. Substance declaration for your information.

Contractual warranty

Warranty	18 months
----------	-----------